

**BNR INFRASTRUCTURE PROJECTS PRIVATE LIMITED**HO : 1018, TVS Colony, 42nd Street, Anna Nagar West,
Chennai, Tamil Nadu-600101

33AAFCB1152J1Z1

SERVICE ORDER

SUPPLIER DETAILS	DELIVERY ADDRESS
ADL COORDINATES PVT LTD (VN05731) B-76,Nice Area,MIDC,Satur,Nashik-422007, Nashik,Maharashtra-422007 27AAXCA6483D1Z6. Contact Person : Akash Singh Contact No :	Service Order No : KWC/23-24/SO/00017 Service Order Date : 01-03-2024 Project Name : KWC
BILLING ADDRESS	DELIVERY ADDRESS
BNR INFRASTRUCTURE PROJECTS PRIVATE LIMITED HO : 1018, TVS Colony, 42nd Street, Anna Nagar West, Chennai, Tamil Nadu 33AAFCB1152J1Z1	Keeranatham Village, Annur Taluk, Annur, Tamil Nadu-641653.

SO Details:

Service	Unit	SAC Code	Qty	Rate	Amount
Consultation charges for Airport Authority of India (AAI) NOC	LS	995412	1.00	75,000.00	75,000.00
Base Amount					75,000.00
CGST Amount 0 %					0.00
SGST Amount 0 %					0.00
IGST Amount 18 %					13,500.00
Total Amount					88,500.00

Amount in Words: Eighty Eight Thousand Five Hundred Only

Narration

1. Payment Terms -

- 50% Advance Payment along with Order
- 30% On Submission of Site Elevation Certificate
- 20% On Approval from AAI

2. The Survey will be conducted within 7 days from the date of receipt of confirmed Work Order.

3. The Survey work will be completed within 2 days from the date of commencement of on ground survey considering the environmental conditions

4. Draft Site Elevation Certificates will be submitted in prescribed format of AAI within 7 days from the date of completion of Survey at Site.

5. On acceptance of draft by you final certificate will be issued.

6. All necessary permission from respective authorities for entry to survey site shall be arranged by the client.

7. All / any power , water and other requirements for conducting the survey shall be in vendor scope.

8. The Survey is conducted as per AAI's data quality requirements. A technical person along with a helper/labourer from your side shall be deputed on site along with survey team to show actual survey location on ground.

9. Survey to be conducted in Trimble R8s, PENTAX G6NI, NAVCOM DGPS SF3040, PENTAX Total Station W- 2801N, R-1501N & Trimble Total Station C5 with 1arc second accuracy for the survey work.

10. Survey will be conducted at all site boundary corners and center point.

11. The Coordinates and Elevation will be in WGS 84, EGM 08 model & AMSL

12 Survey - NOC Survey for AAI Approval

No. of Blocks - 4 (Four)

No. of Co-ordinates - 20 Co-ordinates with ground elevation (In WGS84)

13. On Completion of the survey the data will be processed and the Site coordinates and Elevation Certificate will be prepared and submitted along with other required additional documents with in 3 days for getting signed from your authorized Signatory

On receipt of the signed documents,

- a) Preparation and submission of application to Airport Authority of India
- b) it will be uploaded on the AAI NOCAS site for the approval
- c) Continuous follow up with the department officials
- d) Obtaining NOC from Airport Authority of India 20 to 30 days From the date of application submission

Authorised Signature